

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21545-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 3-34S-6W
2970 feet from S Section Line, 330 feet from W Section Line
Lease Name: RED Well #: 1-3
County: HARPER Total Vertical Depth: 4547 feet

Operator License No.: 31629
Op Name: NASH OIL & GAS, INC.
Address: P. O. BOX 8747
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223		145 SX CMT.

\$ 147.78

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/14/2006 6:00 PM
Plug Co. License No.: 33724 Plug Co. Name: WARREN DRILLING, LLC
Proposal Rcvd. from: GREG KRAUSE Company: WARREN DRILLING, LLC Phone: (620) 933-2040

Proposed Plugging Method: 35 sxs @ 1100'; 35 sxs @ 700'; 35 sxs @ 280'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 02/14/2006 8:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The drill pipe was ran open end to 1100' and 35 sacks of cement were spotted. The drill pipe was pulled to 700' and 35 sacks of cement were spotted. The drill pipe was pulled to 280' and 35 sacks of cement were spotted. The drill pipe was pulled to 60' and cement was circulated to surface. The rathole was circulated with 15 sacks of cement.

60/40 posmix with 4% gel

Acid Service

Perfs:

RECEIVED
KCC DISTRICT #2
JUN 26 2006
WICHITA, KS

Remarks:

Plugged through: DP

INVOICED
7-11-06
2007060047

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
JUL 10 2006
KCC WICHITA

PKT