

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21503-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 20-26S-9W  
330 feet from S Section Line, 990 feet from W Section Line  
Lease Name: BRADY Well #: 1-20  
County: RENO Total Vertical Depth: 4435 feet

Operator License No.: 33650  
Op Name: WEST BAY EXPLORATION CO., INC.  
Address: 13685 S. WEST BAY SHORE #200  
TRAVERSE CITY, MI 49684

String Size Depth (ft) Pulled (ft) Comment  
SURF 8.625 256

\$ 144.14

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2006 12:00 PM  
Plug Co. License No.: 5892 Plug Co. Name: BERENTZ DRILLING CO., INC.  
Proposal Rcvd. from: DENNIS LEFTWICH Company: BERENTZ DRILLING CO., INC. Phone: (620) 583-4343

Proposed Plugging Method: 35 sxs Arb; 35 sxs @ 1450'; 35 sxs @ 950'; 35 sxs @ 300'; 25 sxs @ 60'; 15 sxs in rathole.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE  
Date/Time Plugging Completed: 06/21/2006 3:00 PM KCC Agent: STEVE VANGIESON

RECEIVED  
KCC DISTRICT #2  
JUN 26 2006  
WICHITA, KS

Actual Plugging Report:

Perfs:

35 sacks cement plug was spotted at the top of the Arbuckle at 4380'. The drill pipe was pulled to 1450' and 35 sacks of cement were spotted. The drill pipe was pulled to 950' and 35 sacks of cement were spotted. The drill pipe was pulled to 300' and 35 sacks of cement were spotted. The drill pipe was pulled to 60' and cement was circulated to surface. The rathole was circulated with 15 sacks of cement.

60/40 posmix with 4% gel

Copeland Cement and Acid


INVOICED  
DATE 7-11-06  
NO. 2007060049

Remarks:

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

RECEIVED  
JUL 10 2006  
KCC WICHITA

PKT