

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22159-00-00
Spot: SWNENW Sec/Twnshp/Rge: 17-14S-15W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MUDD A Well #: 3
County: RUSSELL Total Vertical Depth: 3440 feet

Operator License No.: 32286
Op Name: BROWN, RODNEY DBA MJT OIL
Address: BOX 112 115 3RD STREET
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3439	2020	200 SX
SURF	8.625	979	0	450 SX

\$ 111.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2006 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 230 sxs 60/40 pozmix - 10% gel and 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report: _____ Perfs: _____

Sanded back casing to 3380' and topped with 5 sxs cement using a dump bailer.
Cut casing free at 2020'.
Pulled up to 1650' - mixed and pumped 115 sxs cement with 300# hulls.
Pulled up to 950' - spotted 40 sxs cement with 100# hulls.
Pulled up to 450' - spotted 30 sxs cement with 100# hulls.
Pulled up to 150' - circulated cement with 40 sxs.
POOH. Hole full of cement.

RECEIVED
JUL 12 2006
KCC WICHITA

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

7-12-06

2007060059

Form CP-2/3

JUL 10 2006

PCT