

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20939-00-00
Spot: N2NENWSW Sec/Twnshp/Rge: 23-12S-22W
2580 feet from S Section Line, 1320 feet from W Section Line
Lease Name: STANTON Well #: 1
County: TREGO Total Vertical Depth: 4083 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4068	0	200 SX
SURF	8.625	290	0	175 SX

\$ 132.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 275 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2006 10:15 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded well to 4033' with 5 sxs cement.
Unable to pull casing.
Squeezed at 1190' to surface three times to circulate to surface. Amount unknown.
Ran tubing to 1800' - circulated with 140 sxs cement with 300# hulls.
Pulled all tubing and squeezed casing with 40 sxs cement.
Max. P.S.I. 1000#. S.I.P. 1000#.
Squeezed annulus to 500# - took no cement.
Total of 180 sxs 60/40 pozmix - 10% gel and 300# hulls.

Perfs:

Top	Bot	Thru	Comments
4068	4083		
3854	3864		
3679	3699		

RECEIVED
JUL 12 2006
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING. ATS-WATER.

Plugged through: CSG

District: 04

Signed Roger X. Moses
(TECHNICIAN)

INVOICED
7-12-06
2007060060

JUL 07 2006

PRT

JOHN JAY DARRAH, JR. #1 STANTON 23-12-22W
 405 CENTURY PLAZA WICHITA, KS 67202 C N/2 NE SW
 CONTR MALLARD DRILG. CTY TREGO

GEOL _____ FIELD OGALLAH NORTH EXT (1/8 s)
 E 2383 KB CM 1/22/82 CARD ISSUED 7/1/82 IP OIL WELL
 LANS 3697-99

+	+	+
+	+	+
+	+	+

API 15-195-20,939

LOG	TOPS	DEPTH	DATUM
ANH		1796	+ 587
B ANH		1840	+ 543
TOP		3407	-1024
HEEB		3625	-1242
LANS		3655	-1272
ARB		4064	-1681
PBTD		4068	-1685
RTD		4070	-1687
ODTD		4083	-1700

8 5/8" 290/175sx; 5 1/2" 4068/200sx

NO DST'S
 MICT - CO, (ARB OH) DODD 4083, AC 1000
 G, SWB 2 BOPH, BP 4068, PF 3697-99,
 SWB 8 BFPH, 50% OIL, OIL WELL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS