

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20957-00-00
Spot: SESWSWNW Sec/Twnshp/Rge: 23-12S-22W
2759 feet from S Section Line, 4635 feet from E Section Line
Lease Name: NIXON Well #: 2
County: TREGO Total Vertical Depth: 4097 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4081	0	200 SX CMT
SURF	8.625	284	0	200 SX CMT

\$ 133.15

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2006 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 225 sxs cement - 19 sxs gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2006 12:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV at 850' w/400 sxs cement.
Fish at 1600' - milled on fish - no progress.
Ran tubing 1550' - spotted 285 sxs cement with 250# hulls.
Pulled tubing to 775' - circulated with 100 sxs cement with 250# hulls.
Pulled all tubing and squeezed with 150 sxs cement.
TOC fell from 300' to 600' from surface.
Let set overnight.
Tied to 5 1/2" casing and squeezed 80 sxs cement to Max. P.S.I. 300#.
Annulus full to surface with cement.
Total of 615 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
4075	4088		
3660	3670		

RECEIVED
JUL 12 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY, QUALITY WELL & ATS-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

7-12-06
2007060063

JUN 30 2006

PT

