

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21561-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 17-14S-15W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: DORTLAND B Well #: 1  
County: RUSSELL Total Vertical Depth: 3355 feet

Operator License No.: 32286  
Op Name: BROWN, RODNEY DBA MJT OIL  
Address: BOX 112 115 3RD STREET  
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3245	0	125 SX
SURF	8.625	215	0	150 SX

\$ 109.04

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2006 11:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/06/2006 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 1625' and 965'.  
TIH with tubing to 2000'.  
Mixed and circulated cement with 120 sxs with 500# hulls.  
POOH. Swaged onto 5 1/2" and pumped 40 sxs cement.  
S.I.P. 1000#.  
Hooked up to 8 5/8" and pumped 50 sxs cement.  
S.I.P.400#.

RECEIVED  
JUL 12 2006  
KCC WICHITA

Remarks: QUALITY CEMENTING.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICE

DATE 7-12-06

INVOICE NO. 2007.060059

Form CP-2/3

JUL 10 2006

PKF

CRUDE PRODUCERS, INC. REPLACEMENT CARD# 17-14-15W  
 P. O. BOX 55 #1 DORLAND "B" NW 1/4 1/4  
 RUSSELL, KS. 6/88  
 COVER REFIN DRILLING INC. RUSSELL

GEOL BRAD HUTCHINSON FIELD WCG W OF CORHAM  
 # 1868 KB 10/18/80 CAPT 12/11/80 SEP BY DEY HOLES  
 LKO 3088-3079 OA

AP# 15-167-21,56'

DATE	DEPTH	DATUM	REMARKS
			8-5/8" 215/506x, 52" 3245/236x
			NO 26" S REPORTED
			W.C. - CO. BE (LKO) 16/3088-22
			16/3012-15, 24/3129-OA, AC 250' (15%)
			ALL ZNS COMMUNICATED, SWB LD, BE-AC
			2000' @ (15% VE) 16/3156-60, SWB, DWY W/
			650' @ (LKO) 16/3156-60, 12/3169-70
			AC 250' @ (15%) SWB LD SWB 10 BEP,
			10' @ AVRS, 10' @ 30' 30' 30' 30' 30'
			10/28/80

INDEPENDENT OIL & GAS SERVICES  
 WICHITA, KANSAS

INFO RELEASED: 10/1/80 - WAS OIL WELL -  
 DRY HOLE

17-14-15W  
 NW NW NE

"B"

107-14-15W

107-14-15W