

State of Kansas



15-141-20011-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

8-26-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Vail of Neven H. Vail has this

date requested permission to plug the following described well:

Mr. Vail guarantees payment of the plugging fee.

Operator's full Name: Neven H. Vail

Complete Address: 1401 McKinley Great Bend, Ks.

Lease Name: Snyder Well No. I

Location: C SW NW Sec. 4 Twp. 8 Rge. 14 (E)(W) X

County: Osborne Total Depth 3850 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Vail was instructed to plug the well as follows:

Run pits, circulate heavy mud, set cementing plug at 450' and displace  
50 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Red F. Massey  
Conservation Division Agent