



15-141-20053-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 4 1978

CONSERVATION DIVISION  
Wichita, Kansas

12/4/78

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of Pioneer Drilg. Co., Inc. has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 400 N. Woodlawn, Suite 210 Wichita, Kansas

Lease Name: Bliss Well No. 2

Location: SW SE SW Sec. 14 Twp. 8 Rge. 14 (~~EX~~(W) X

County: Osborne Total Depth 2840' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Moore was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 540'.

Fill hole with mud and spot 25 sx cement at 200'.

Fill hole with mud to 40' & 1/2 sx hulls, plug, & 10 sx cem.  
2 sx cement in rat hole.

198' of 8 5/8" surface casing cement circ.

Very truly yours,

Deane J Rankin  
Conservation Division Agent