

State of Kansas



15-141-00007-00-01

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1974

CONSERVATION DIVISION  
Wichita, Kansas

12-2-74

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sam Waggoner of Red Tiger Drilling Co. has this  
date requested permission to plug the following described well:

Mr. Billy Morris guarantees payment of the plugging fee.

Operator's full Name: Morris & Morris

Complete Address: 112 Ober Street, Russell, Kansas 67665

Lease Name: Habiger Well No. # 1

Location: NW NW SE Sec. 27 Twp. 8 Rge. 15 (E)(W) W

County: Osborne  
Russell Total Depth 1240 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Sam Waggoner was instructed to plug the well as follows:

8 5/8" csg. 158' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 185' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don L. Luman  
Conservation Division Agent