



15-141-20016-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

10-17-1972

CONSERVATION DIVISION
Wichita, Kansas

10-17-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. A. J. Joiner of Petroleum Management, Inc. has this date requested permission to plug the following described well:

Mr. Petroleum Management, Inc. guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: Box 922, Great Bend, Kansas 67530

Lease Name: McReynolds Well No. # 1

Location: SE SW NW Sec. 30 Twp. 8 Rge. 15 (E)(W) W

County: Osborne Total Depth 3455 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mike Wassinger was instructed to plug the well as follows:

8 5/8" csg. 240' Cwc. Perf. 2935'.

Sanded hole back to 2900' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20 sax mud, 1 sax hulls, & 100 sax

cement with Allied Cementing Company's pump truck, cementing from

340' to base of cellar.

Very truly yours,

Dore L. Luman
Conservation Division Agent