



15-141-20134-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

April 20, 1982

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1982

4-26-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
Conservation Division
Wichita, Kansas

Dear Sir:

Mr. Vernon Zorn of Shields Drilling Co, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers, Inc.

Complete Address: Shields Building, Russell, Kansas 67665

Lease Name: Schneider Well No. 1

Location: NW NW NE Sec. 31 Twp. 8 Rge. 15 (E) (W)

County: Osborne Total Depth: 3570'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Zorn was instructed to plug the well as follows:

Anhydrite 1233-68 Elev. 1957 KB Circulate hole and Fill with mud.
Pump 50 sacks cement through drill pipe at 930'. Pump 30 sacks
Cement through drill pipe at 250'. Fill hole with mud to 40'.
Push plug and 1/2 sack balls to 40' and cap hole with 10 sacks
Cement. Cement rat hole with 10 sacks cement. Cement mouse hole
with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent