



15-141-20137-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

June 23, 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Vernon Zorn of Shields Drilling Co., Inc has this date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name: Schneider Well No. 2

Location: NE NE SE Sec. 31 Twp. 8 Rge. 15 (E) (W)

County: Osborne Total Depth: 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Zorn was instructed to plug the well as follows:

Elev. 2013-KB Anhydrite 1294-1325 Circulate hole and
Fill with mud. Pump 50 sacks cement through drill pipe
at 990'. Pump 40 sacks cement through drill pipe at
300'. Fill hole with mud to 40'. Push plug and 1/2 sack
hulls to 40' and cap hole with 10 sacks cement. Cement rethole
with 10 sacks cement. Cement mouse hole with 10 sacks cement.

Very truly yours,

William J. Larson
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1982

CONSERVATION DIVISION
Wichita, Kansas

7-1-82