

State of Kansas



FORM CP-2

15-141-20118-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

October 23, 1981

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Harold Maley of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Midea Exploration, Inc.  
Complete Address: 411 Farmers and Bankers Bldg, Wichita, Kansas 67202  
Lease Name: Koelling Well No. 1  
Location: C SW NW Sec. 36 Twp. 8 Rge. 15 (W)  
County: Osborne Total Depth: 3875'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereafter indicated: \_\_\_\_\_

Mr. Maley was instructed to plug the well as follows:

8 3/8" - 245' circ. Elev 1888 KB unable to pick up any Anhydrite  
Circulate hole and fill with mud. Pump 50 sacks cement  
through drill pipe at 900'. Pump 50 sacks cement through  
drill pipe at 310'. Fill hole with mud to 40'. Push plug  
and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.  
Cement rat hole with 10 sacks cement.

Very truly yours,

[Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 23 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
10-26-81