

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NW NW

SEC. 8 TWP. 8 RGE. 17 *W*

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-1 Lease Turner

Operator Murfin Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 5550 Feet.

Plugging Contractor Earl Miller

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement. 5 1/2" at 5546' with 50 sax cement behind.

Chat to 5550', set 4 sax cement with dump bailer, pulled 2900' 5 1/2", pumped hole full mud (35) sax, pumped cementing plug to 220', followed by 70 sax cement. Cement 220' to 0'.

Mudding and cementing by Sun Cementing Co.

Edna Petty

District Conservation Agent

Date 3-26-54

PLUGGING
FILE SEC 8 T 8 R 12W
BOOK PAGE 23 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1954
CONSERVATION DIVISION
WICHITA, KANSAS