

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 5, 1971 APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Schindler "A" Well No. 1

Location SE SW NE Sec. 16 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3435'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Go. Tools

Address License No.

Operation Completed: Hour 2 P Day 4 Month 4 Year 1971

The above well was plugged as follows:

RTD 3435' 8 5/8 csg set at 241' cwc Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lawrence M. Manning
Well Plugging Supervisor

INVOICED

DATE
INV. NO.