

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 129-36

LOCATION NW SW NW

SEC. 9 TWP. 8 RGE. 17W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 45 Lease _____ Arndts _____

Operator V. D. Sidey Oil Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3370 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 105' circulated with cement - 5 1/2" at 3365' with 100
sax cement behind - P. B. to 3220', perforated at 3170'
Filed with sand to 3160', set 4 sax cement with dump bailer,
pulled 2730' 5 1/2" - pumped hole full mud (35 sax Gel)., pumped
cementing plug to 230' followed by 70 sax cement - cement 230' to 0'.
Mudding and cementing by Halliburton Co.

PLUGGING
FILE NO. 9 T 8 R 12 W
BOOK PAGE 129 LINE 36

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1957
JAN 31 1957
CONSERVATION DIVISION
Wichita, Kansas

E. Kelly
District Conservation Agent
Date 1-30-57