

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 19-3

LOCATION NW NW NW

SEC. 9 TWP. 8 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease _____ Arndts _____

Operator V. D. Sidey Oil co Address Russell, Kans

Field _____ County Rooks

Total Depth 3392 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 116' circulated with cement - 5 1/2" at 3390' with 100 sax cement behind.

Filled with sand to 3380', set 4 sax cement with dump bailer, pulled 2730' 5 1/2" - pumped hole full mud (30 sax Jel) - pumped cementing plug to 200', followed by 60 sax cement.

Mudding and cementing by Halliburton Cementing Co.

JAN 3-1956

District Conservation Agent

Date 12-31-55

PLUGGING
FILE SEC 9 T 8 R 17W
BOOK PAGE 19 LINE 3