



KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1964
Sept. 29th 1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tomlinson - Kathol Inc
Complete Address: 1125 Wichita Plaza Wichita, Kansas
Lease Name Schindler Well No. 1
Location NE NW NE Sec. 17- Twp. 8 Rge. (E) (W) 17
County Rooks Total Depth 3370
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kansas License No. 436
Operation Completed: Hour 10AM Day 26 Month 9 Year 64

The Above well was plugged as follows:

8 5/8 ? - 5 1/2" 3358' with 100 sax cement.
PB to 3195' Perf 3086'

Set plug at 3070' sand and 4 sax cement - pulled 2100' 5 1/2" to 500'
circulated hole with heavy mud through 5 1/2" at 500' - displaced 20 sax
cement through 5 1/2" at 500' - heavy mud to 200' - displaced 20 sax
cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: E. J. Perry
Well Plugging Supervisor

DATE 9-29-64

INV. NO. 9889-W