

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 553 Russell, Kansas 67665

Lease Name Chesney Unit Well No. 101 W

Location C SE SW NW Sec. 12 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3416'

Abandoned Oil Well Gas Well Input Well XX SWD Well D & A

Other well as hereafter indicated: Co. Tools By HOWCO

Plugging Contractor: Hays, Ks.

Address: License No.

Operation Completed: Hour 2P Day 21 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 3416' 8 5/8 csg set at 239' cwc 175 sk.

5 1/2 csg set at 3415' cw 225 sk cmt.

5 1/2 csg PBD 3363' Perf. (2847-3299)

5 1/2 DV tool set at 1252' cwc 500 sk. No Pipe Recovered

Tubing to 3034' circulated 32 sk gel W/3 sk hulls.

Displaced 100 sk 50-50 poz cmt 2% (2026-3034)

Tubing to 617' Displaced 15 sk cmt. (467-617)

Tubing to 216' circulated 35 sk cmt. (0-216)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. F. M. [Signature]
Well Plugging Supervisor

DATE 4/23/69
INV. NO. 9651-W