



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1974  
JUN 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Black Petroleum Co.

Complete Address 545 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Schlinder Well No. 1

Location NE NE SE Sec. 16 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3450'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Shields Drlg.

Address Russell, Kansas License No.       

Operation Completed: Hour 9 A. Day 31 Month 5 Year 1974

The above well was plugged as follows:

RTD 3450' 8 5/8 csg set at 284' cwc 150 sk. Cmt. Mat. 50-50 pez W/6% total Gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Marney  
Well Plugging Supervisor

INVOICED

DATE 6/5/74  
INV. NO. 9242-W