

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1962
JUN 12 1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: a Rooks

Location: SW SW SW Sec. 17 Twp. 8 Rge. _____ (E) _____ (W) 17

Name of Field: _____ Total Depth: 3340

I have this date completed supervision of plugging of:

Lease Name: Schindler Well No. 1

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kansas

Plugging Contractor Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 7 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 135' circulated with cement - 5 1/2" 3329' with 75 sax cement.

Hole in 5 1/2" in Dakota section - filled with sand to 3310', set 4 sax

cement with dump bailer - pulled 990' 5 1/2" to 550' - circulated hole

with 20 sax Gel & 20 sax weit mud - displaced 20 sax cement through

5 1/2" at 550', heavy mud to 150', set 20 sax cement at 150', heavy

mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Ace Pipe Pulling pump truck.

Signed: Eason Lacey
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED
DATE 6/13/62
INV. NO. 5170-W