

KANSAS

*af* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1971 *May 17, 1971*  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center Wichita, Kansas

Lease Name Maddy Well No. 1

Location SE SE SW Sec. 18 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3418'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 2:30 P Day 15 Month 5 Year 1971

The above well was plugged as follows:

RTD 6 3/4 hole to 3418' 7 3/8 csg set at 219' cwc Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 40 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 15' sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sk hulls and 8 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo J. Massey*  
Well Plugging Supervisor

DATE 5/17/71  
INV. NO. 3711-11