

KANSAS

*AL* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1971 JUL 23, 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name J. Mark Richardson

Complete Address 200 W. Douglas Wichita, Kansas

Lease Name Schindler Well No. 1

Location NE NE SE Sec. 18 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3390'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Gabbert & Jones, Inc.

Address Wichita, Kansas License No.       

Operation Completed: Hour 5 P Day 19 Month 7 Year 1971

The above well was plugged as follows:

RTD 3390' 8 5/8 csg set at 209' cwc 150 sk. Cmt. Mat. 50-50 reg. poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo J. Massey*  
Well Plugging Supervisor

DATE 7-23-71

INV. NO. 4043-W