

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
AUG 17 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil Company

Complete Address Route 2 Victoria, Kansas

Lease Name Schindler Well No. 1

Location SE SW NW Sec. 17 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3327'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 11:30 P Day 13 Month 8 Year 1972

The above well was plugged as follows:

RTD 3327' 8 5/8 csg set at 263' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: P. G. Massey
Well Plugging Supervisor

INVOICED

DATE 8/21/72
INV. NO. 6204-w