

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 163-20394-00-00 (of this well)

Operator's Full Name ENERGY RESERVES GROUP, INC.

Complete Address 925 PATTON ROAD, GREAT BEND, KANS. 67530

Lease Name RAY, SCHINDLER Well No. #2

Location SE-SW-SW Sec. 17 Twp. 8 Rge. 17 (E) (W) W

County ROOKS Total Depth 3316 FT

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor HALLIBURTON SERVICES

Address EAST 8TH ST. HW-40 HAYS, KANS. License No.

Operation Completed: Hour 3:30 PM Day 9TH Month MAY Year 1980

The above well was plugged as follows:

8 5/8" 245^{FE} SD. CUC w/ 175^{SE} CMT. -> 5 1/2" SET AT. 3316^{FE} w/ 1200^{SE} CMT.

SQUEEZED AT. 3305^{FE} w/ 142^{SE} CMT.

PERFS - 3305' - 3307' TO 3311^{FE} -> 3040' TO 3043^{FE} -> 3081^{FE} TO 3084^{FE}

3195' TO 3198^{FE} -> PACKER + TUBING SANDED IN HOLE AT 3030^{FE}

PLUGGED SOLID AT BOTTOM. - TUBING PARTED AT 2722' - 2720' DAKOTA BROWN IN

ORDERED 175^{SE} 150 PORMIX 6% GEL. -> AND 7^{SE} HULL'S

PUT IN 3^{SE} HULL'S -> 145^{SE} CMT WITH 4^{SE} HULL'S PUT IN CMT.

AND .30^{SE} IN ANNULUS. -> ANNULUS MAX. PRESSURE 450^{PSI} SET AT 250^{PSI}

5 1/2" MAX PRESSURE 375^{PSI}

I hereby certify that the above well was plugged as herein stated.

(CEMENTED BY HALLIBURTON)

INVOICED

DATE 5-13-80

INV. NO. 2530W

Signed: Marvin Schmitt
Well Plugging Supervisor

RECEIVED
MAY 13 1980
CONSERVATION DIVISION
Wichita, Kansas