

State of Kansas



15-163-20048-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1967

D-10-67  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Moore of C & G Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C-G Drilling Company

Complete Address: 107 Rule Bldg. Wichita, Kansas

Lease Name: Hrabe "A" Well No. 2

Location: NE SW SW Sec. 7 Twp. 8 Rge. 17 (E)(W) X

County Rooks Total Depth 3406 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1040' and displaced  
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with  
20sc cement.

Very truly yours,

Geo F. Massey  
Conservation Division Agent