

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Wilson Rains guarantees payment of the plugging fee.

Operator's full Name: Rains-Williamson Oil Company, Inc.

Complete Address: 1425 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Stamper Well No. # 1

Location: NW NW NW Sec. 16 Twp. 8 Rge. 17 (E)(W)W

County: Rooks Total Depth 3385 Oil Well

Gas Well      Input Well      AWD Well      D & A X Lost Hole     

Mr. Art Hunt was instructed to plug the well as follows:

8 5/8" 215' Cwc. wh/165 sax.  
Circulated hole with heavy mud to 600', set plug, & displaced 70 sax  
cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru  
drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax  
cement with Globe Cementing Company's pump truck, cementing to base

of cellar.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 1, 1969 JUL 1 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

Very truly yours,

Don L. ...  
 Conservation Division Agent