

State of Kansas



GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1959
JUL 20 1959
CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 7-9-59, 1959, authorized the following plugging operation:

Operator's Full Name: Cities Service Co

Complete Address: Box 751 Great Bend, Kans

Lease Name: Chesney Well No. B-3

Location: NW SE SW Sec. 12 Twp. 8 Rge. 17 (E) (W)

County: Rooks Total Depth: 3340

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

8 5/8" at 240' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 540', displaced

20 sax cement through drill pipe, heavy mud to 180', set plug and

20 sax cement, mud to 40', set plug, hulls and 10 sax cement.

Very truly yours,

Signed: *Edon Petty*
Conservation Division Agent