


State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 08 1976
MAR 08 1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Niernberger of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie

Complete Address: 412 Union Center Bldg., Wichita, Ks.

Lease Name: Schindler Well No. 1

Location: Appr. NW NW NE Sec. 17 Twp. 8 Rge. (E)(W) 17

County: Rooks Total Depth 3335' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 160' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent