

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1967
MAR 22nd 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Wylor of Shields Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Wylor guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: 1117 Wichita Plaza Wichita, Kansas

Lease Name: Maddy Well No. 1

Location: NW NW NW Sec. 18 Twp. 8 Rge. 17 (E)(W) X

County Rooks Total Depth 3420 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wylor was instructed to plug the well as follows:

Run pits, circulate heavy mud, set cementing plug at 480' and displace
20 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and
diaplace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Luo Massey
Conservation Division Agent