

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: COLT ENERGY, INC
Address: P O BOX 388, IOLA, KS 66749
Phone: (620) 365-3111 Operator License #: 5150
Type of Well: GAS LIT KCC 7117106 PKT per Jim
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6-26-06 (Date)
by: ALAN DUNNING (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
SEE ATTACHED Depth to Top: _____ Bottom: _____ T.D. _____
DRILLERS LOG Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-099-23,876 ~~00-00~~
Lease Name: ENEGREN
Well Number: 5-1
Spot Location (QQQQ): APPE/2 - SE - SW - NW
2300 Feet from North / South Section Line
1160 Feet from East / West Section Line
Sec. 1 Twp. 31 S. R. 17 East West
County: LABETTE
Date Well Completed: NOT COMPLETED LOST BIT IN HOLE
Plugging Commenced: 6-26-06
Plugging Completed: 6-27-06

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	SURFACE			8 5/8	20	NONE
RECEIVED JUL 14 2006 KCC WICHITA						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

6-26-06 RAN 2" 8RD PLUGGING STRING TO 720' HIT FILLUP HUNG ON CLAMP. 6-27-06 WASHED 2" DOWN FROM 720' TO 969' 6-27-06 CONSOLIDATED PUMP 10SXS 60/40 POZ-MIX CEMENT @969' PULLED UP FILLED WITH GEL TO 625' PUMPED 10SXS CEMENT @625' PULLED UP FILLED W/GEL TO 250' PUMPED 50SXS CEMENT FROM 250' TO SURFACE PULLED 2" OUT WELL IS PLUGGED.

Name of Plugging Contractor: CONSOLIDATED OIL WELL SERVICES, INC License #: 31440
Address: P O BOX 884 CHANUTE, KS 66720
Name of Party Responsible for Plugging Fees: COLT ENERGY, INC
State of _____ County, _____, ss.

_____, (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Dennis Herschler
(Address) P O BOX 388 IOLA, KS 66749

SUBSCRIBED and SWORN TO before me this 12th day of July, 2006
Shirley A Stotler My Commission Expires: 1-20-2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT