

RECEIVED

JUL 14 2006

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Scheck Oil Operation

Address: 225 Main Street Russell, KS 67665

Phone: (785) 483-3404 Operator License #: 9292

Type of Well: Oil Docket #: _____ (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-02118-00-00

Lease Name: Maes

Well Number: 1

Spot Location (QQQQ): _____ - SW - NW - SW 1650 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 14 Twp. 19 S. R. 9 East West

County: Rice

Date Well Completed: 10-30-43

Plugging Commenced: 6-26-06

Plugging Completed: 6-27-06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten entries for 'Surf Prod' with casing sizes 8 5/8 and 5 1/2.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded bottom to 2900' with 5sx. cement, perforated well @ 1500', 800', & 260'. Ran in 2 3/8 tubing to 1150', mixed 35sx. cement, pulled to 800' and mixed 35sx. cement, pulled to 260', mixed 50sx. cement, no circulation. Layed down tubing, Ran back to 260' with 300lbs. hull, 5sx. gel and 100sx. cement, cement circulated out of surface & longstring. Topped with 15sx. cement 60/40poz. 4% gel

Name of Plugging Contractor: Mike's Testing & Salvage License #: 31529

Address: P.O. Box 467 Chase, KS 67524

Name of Party Responsible for Plugging Fees: Scheck Oil Operation

State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED and SWORN TO before me this 3rd day of July, 2006

Irene Herzberg Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials 'PK'