

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUL 14 2006

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mike Kelso Oil, Inc.
Address: P.O. Box 467
Phone: (620) 938-2943 Operator License #: 31528
Type of Well: Oil EOR Per RBBS Plan KCC Docket #: E-13617
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-00477-00-01
Lease Name: Sanders
Well Number: 1
Spot Location (QQQQ): _____ - NE - NW - NW
4950 Feet from North / South Section Line
4250 Feet from East / West Section Line
Sec. 1 Twp. 25 S. R. 14 East West
County: Stafford
Date Well Completed: 4-11-58
Plugging Commenced: 5-15-06
Plugging Completed: 5-16-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Surf</u>				<u>8 5/8</u>	<u>310</u>	<u>none</u>
<u>Prod</u>				<u>5 1/2</u>	<u>4324</u>	<u>1800'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Found BP @ 3550' and dumped 2sx. cement on BP. Pulled stretch 25", cut casing @ 2600' and 2400', 2000', & 1800'. Worked casing loose, pulled up to 1000', mixed 15sx. gel & 50sx. cement, pulled to 500', mixed 50sx., pulled to 40' and circulated to surface with 50sx. cement. 60/40poz. 6%gel

Name of Plugging Contractor: Mike's Testing & Salvage License #: 31529
Address: P.O. Box 467 Chase, KS 67524
Name of Party Responsible for Plugging Fees: Mike Kelso Oil, Inc.
State of Kansas County, Rice, ss.
Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED and SWORN TO before me this 3rd day of July, 2006
Irene Herzberg My Commission Expires: _____
Notary Public

