

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-01274-00-00

Spot: S2S2NESE

Sec/Twnshp/Rge: 16-34S-14E

1520 feet from S Section Line,

660 feet from E Section Line

Lease Name: HECHT

Well #: 7

County: MONTGOMERY

Total Vertical Depth: 750 feet

Operator License No.: 31486 •

Op Name: HORTON, JACK

Address: PO BOX 97
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	750		
SURF	6.625	20		

\$ 35.00

Well Type: EOR

UIC Docket No: E10442.1

Date/Time to Plug: 05/26/2006 8:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ELMORE

Company: ELMORE'S, INC

Phone: (620) 725-5744

Proposed
Plugging
Method:

Run a one inch cement string to TD. Fill with cement from bottom to top.

Plugging Proposal Received By: LARRY MARCHANT

WitnessType: NONE

Date/Time Plugging Completed: 05/26/2006 12:00 AM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A one inch cement string was run to 750 ft. 5 bbls of gel water was mixed and 10 sacks of portland cement with cotton seed hulls was spotted on bottom. The one inch cement string was raised to 350 ft and 35 sacks of portland cement circulated to surface. A total of 45 sacks of portland cement were used to plug well.

RECEIVED
KCC DISTRICT

JUL 5 2006

CHANUTE, KS

AMD

INVOICED
DATE 7-14-06
TR. NO. 2007060203

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

RECEIVED

JUL 13 2006

KCC WICHITA

Form CP-2/3

PKT