

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20182-00-00
Spot: SENE Sec/Twnshp/Rge: 12-3S-14E
3300 feet from S Section Line, 810 feet from E Section Line
Lease Name: GEORG Well #: 8-12
County: NEMAHA Total Vertical Depth: 2745 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2720	1170	205 SX CMT
SURF	8.625	271		137 SX CMT

\$ 89.21

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/10/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GLE FROM 2672' TO 2533' CEMENT FROM 2533' TO 2120' GEL FROM 2120' TO 300' CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 01/11/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-10-06 ran tubing and tagged bottom at 2597'. Moved up to 2593' and spotted 2 barrels of gel, gel placed from 2593' to 2528'. Moved tubing up to 2528' and pumped 45 barrels of gel and 50 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2528' to 2090' and gel from 2090' to 300'. Returned to well on 1-11-06 and shot the casing off at 1170'. Pulled casing to 302' and circulated 90 sacks of cement from 302' to surface and pulled the casing.

Perfs:

Top	Bot	Thru	Comments
2482	2483		
2423	2425		
2404	2406		
2394	2398		
2356	2358		
2307	2309		
2212	2214		
2170	2172		

RECEIVED
KCC DISTRICT #3

JUL 7 2006 TCH
CHANUTE, KS

INVOICED

DATE 7-14-06
2007060202

Remarks:

Plugged through: TBG

District: 03

RECEIVED
JUL 13 2006
KCC WICHITA

Signed

Taylor Herman

(TECHNICIAN)

PKT