

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-29266-00-00

Spot: SESENE

Sec/Twnshp/Rge: 13-25S-18E

2990 feet from S Section Line,

350 feet from E Section Line

Lease Name: BARNETT

Well #: 13-1

County: ALLEN

Total Vertical Depth: 1088 feet

Operator License No.: 33221

Op Name: ROXANNA PIPELINE, INC.

Address: 4600 GREENVILLE AVE., SUITE 200  
DALLAS, TX 75206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD   | 5.5  | 1087       | 0           |         |
| SURF   | 8.25 | 20         | 0           |         |

# 35 36

Well Type: OG

UIC Docket No:

Date/Time to Plug: 03/07/2006 9:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY

Proposal Rcvd. from: TOM GILBERT

Company: ROXANNA PIPELINE, INC.

Phone: (214) 691-6216

Proposed Plugging Method: THIS WELL CONSISTED OF 5 1/2" CASING TO 1087' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SAND BACK THE PERFORATIONS AND TO CIRCULATED THE 5 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/07/2006 11:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

2" TUBING WAS RAN INTO THE 5 1/2" CASING TO TD. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

| Top | Bot  | Thru | Comments |
|-----|------|------|----------|
| 986 | 1003 | CSG  |          |

RECEIVED  
KCC DISTRICT #3

JUL 5 2006 CPT

CHANUTE, KS

INVOICE

7-14-06

2007060207

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel  
(TECHNICIAN)

RECEIVED

JUL 13 2006

KCC WICHITA

PKT