

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24209-00-00
Spot: SWSESW Sec/Twnshp/Rge: 18-16S-22W
420 feet from S Section Line, 1720 feet from W Section Line
Lease Name: KEITH Well #: 1
County: NESS Total Vertical Depth: 4520 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1824		CMT TO SURFACE
PROD	5.5	4518	0	WITH 100 SX CMT
SURF	8.625	227		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2006 9:50 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: PUMP 200# HULLS & 35 SX CMT WITH GEL SPACER. PLUG THROUGH TUBING @ 1850' TO SURFACE WITH 165 SX CMT. 50 SX CMT TO PRESSURE BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2006 6:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

06/21/06: PUMPED 200# HULLS & 35 SX CMT FOLLOWED BY 15 SX GEL. CASING PRESSURED TO 900#. PRESSURED BACKSIDE. 06/28/06: RAN TUBING TO 1120' & PUMPED 110 SX CMT. CIRCULATED TO SURFACE. PULLED TUBING AND TOPPED OFF WITH 15 SX CMT. CASING STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4443	4447		
4439	4442		

RECEIVED
JUL 17 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 0



Signed

Michael J Maier
(TECHNICIAN)

INVOICED
DATE 7-18-06
INV. NO. 2007060223

Form CR 2/05

Handwritten initials/signature