

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-~~26857~~-00-00

26900-00-00

28 KCC  
Peroperator  
contact 7.19.06

Spot: ~~SENE~~ SENE

Sec/Twnshp/Rge: 24-24S-15E

3125 ~~380~~ feet from S Section Line, ~~280~~ feet from E Section Line

Lease Name: BOWERS

Well #: 17

County: WOODSON

Total Vertical Depth: 1170 feet

Operator License No.: 32079

Op Name: LEIS, JOHN E.

Address: 111 E. MARY  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	10 SX CMT

# 38<sup>03</sup>

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/22/2005 8:00 AM

Plug Co. License No.: 32079

Plug Co. Name: LEIS, JOHN E.

Proposal Rcvd. from: JOHN LEIS

Company: LEIS, JOHN E.

Phone: (620) 496-6946

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1170'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 600', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

Witness Type: NONE

Date/Time Plugging Completed: 08/22/2005 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

PIPE WAS RAN INTO THE WELL TO 1160'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 1160'. THE PIPE WAS PULLED TO 600' AND 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 600'. THE PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. ALL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
KCC DISTRICT #3

~~FEB 8 2006~~  
9-9-2005 CPT  
CHANUTE, KS

RECEIVED  
~~FEB 15 2006~~  
9-19-2005  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

INVOICED

DATE 2-15-06 9-21-05

INV. NO. 200606119 2006060463