

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20039-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 2-4S-23W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HARTING Well #: 4
County: NORTON Total Vertical Depth: 3710 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD.
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3703	0	w/unknown sxs cmt
SURF	8.625	244	0	w/unknown sxs cmt

\$ 120.58

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2006 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WILLIAM BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 07/07/2006 1:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfed at 2020' - 1100' - 295'.
Ran tubing to 2400' - pumped 100 sxs 60/40 pozmix - 10% gel with 100# hulls.
Pulled tubing to 1000' - mixed and pumped 70 sxs 60/40 pozmix - 10% gel with 100# hulls - cement circulated.
Pulled tubing - pumped onto backside - blew casing.
Pumped 40 sxs 60/40 pozmix - 10% gel down 5 1/2" casing with 100# hulls. Max. P.S.I. 500#.
Cement circulated up annulus. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3473	3478		

INVOICED
DATE 7-20-06
2007060230

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed

Bruce D. Basye

(TECHNICIAN)

JUL 18 2006

RECEIVED
JUL 19 2006
KCC WICHITA

Form CP-2/3

PAT