

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20081-00-01
Spot: NWSESE Sec/Twnshp/Rge: 36-9S-20W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: PYWELL Well #: 3
County: ROOKS Total Vertical Depth: 1609 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W ROAD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1609	0	477 SX CMT
SURF	8.625	165	0	W/UNKNOWN SXS CMT

\$52.29

Well Type: SWD UIC Docket No: D20291.0 Date/Time to Plug: 07/14/2006 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WILLIAM F BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 885-4830

Proposed Plugging Method: Ordered out 110 sxs 60/40 pozmix - 10% gel - 500# hulls.
Bad pipe at 880' - washed thru bridge to 1356' - lost circulation.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2006 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1305'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 500# hulls - circulated cement.
PTOH. Squeezed 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
1304	1386		

INVOICED
DATE 7-20-06
WEL. NO. 2007060231

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

JUL 18 2006

RECEIVED
JUL 19 2006
KCC WICHITA

Form CP-2/3

PKT

1330:0

replacement card

H & H INVESTMENTS
HAYS KS

36-09S-20W
NW SE SE

#3-SWD PYWELL

site 1/2 S & 3 W OF ZURICH KS city: ROOKS API 15-163-21175
 contr: SUPERIOR WELL SVC field: MARCOTTE

fr date 10/24/1980 spd date 10/26/1980 drig comp 11/01/1980 card issued 07/02/1981 test revised 11/13/2000

ELV: NA

tops.....	depth/datum
PBTD.....	1609
RTD.....	3819
NO TOPS RPTD	

IP status:
 SWDW, CED HILL 1302-1386 , 02/05/1982
 CORR & INFO REL: 11/13/2000 - ORIG FR AS LAWBANCO
 DRILLING AS OPERATOR; WAS SWDW - TEMP COMP
 CSG: 8-5/8" 227, 4-1/2" 1609
 COMMENT: NO SIGNFCNT SHOWS ENCNTRD
 NO CORES OR DSTS
 SI - EVAL FOR SWD USE (11/2/1980), RE-ACTIVATED
 2/1/1982, MICT - CO, PB 1609, PF (CED HILL) 1302-1386, NO
 TRTMNT, COMP AS SWDW - INJECTION RATE
 SATISFACTORY (DKT # 20,291), 2/5/1982