

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-21250-00-00

Spot: NWNWNE

Sec/Twnshp/Rge: 17-25S-9E

250 feet from N Section Line, 2390 feet from E Section Line

Lease Name: HENDRICKSON

Well #: 8

County: GREENWOOD

Total Vertical Depth: 2375 feet

Operator License No.: 5697

Op Name: JACKSON BROS., L.L.C.

Address: 116 EAST THIRD ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2321	682	50 SX CMT.
SURF	7	65		30 SX CMT.

\$ 77.19

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/21/2006 8:00 AM

Plug Co. License No.: 5684

Plug Co. Name: SAGE, LARRY GEORGE

Proposal Rcvd. from:

Company:

Phone:

Proposed
Plugging
Method:

50' CEMENT PLUG @2200' 50' CEMENT PLUG @ 1000' 250' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/23/2006 12:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

BUILT ROCK BRIDGE @ 2232' MIXED & DUMPED 5 SXS. CEMENT WITH DUMP
BALER, SHOT CASING @ 844' COULD NOT PULL CASING, RESHOT CASING @ 640'
PUMPED 25 SXS CEMENT, PULLED CASING TO 266' PUMPED 100 SXS CEMENT TO
SURFACE GEL SPACERS BETWEEN CEMENT PLUGS, CEMENT FELL BACK IN
CASING TOPPED WELL OFF WITH 15 SXS CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2237	2249		

INVOICED
DATE 7-20-06
INV. NO. 2007060232

RECEIVED
KCC DISTRICT #3

JUL 17 2006 *MH*

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

RECEIVED

JUL 19 2006

KCC WICHITA

Mike Heffern
(TECHNICIAN)

PH