

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Meritage KCM Exploration, LLC
Address: 1050 17th Street Suite 975 Denver, Colorado 80265
Phone: (303) 534-9513 Operator License #: 33138
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: April 12, 2006 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
See attached sheet Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-003-24234-00-00
Lease Name: Lankard
Well Number: 34-41
Spot Location (QQQQ): S 2 - NE - NE
900 Feet from North / South Section Line
860 Feet from East / West Section Line
Sec. 34 Twp. 19 S. R. 19 East West
County: Anderson
Date Well Completed: 10/13/03
Plugging Commenced: 5/30/06
Plugging Completed: 5/30/06

KCC 7/18/06
ACT Per CP-1

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface casing		0'	22'	8 5/8"	10/07/03	--
Long string		0'	1201'	5.5"	10/9/03	--

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump down tubing & circ up csg. Mix & pump 109 sks 60/40 Poz mix cement w/4% premium gel down tubing. Circulate cement PBTD to surface. Pull tubing out of well. Top off casing w/10 sks cement.

Name of Plugging Contractor: Consolidated Oil Well Services License #: 31440
Address: 1322 S. Grant Chanute, Kansas 66720
Name of Party Responsible for Plugging Fees: Meritage KCM Exploration, LLC
State of Kansas County, Anderson, ss.
Larry Bryant

RECEIVED
JUL 17 2006
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry Bryant
(Address) 115 North Oak Garnett, Kansas 66032

BARBARA A. WISEHART
NOTARY PUBLIC
STATE OF COLORADO

Subscribed and SWORN TO before me this 10th day of July, 20 06
Barbara A. Wisheart My Commission Expires: _____
Notary Public

My Commission Expires 04/26/2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ACT

Lankard 34-41

Formation	Depth
Stark Shale	382'-385'
Hushpuckney	418'-421'
Muyaka Shale	595'-597'
Mulberry Coal	668'-670'
Anna Shale	702'-704'
Little Osage Shale	751'-753'
Mulky Coal	777'-779'
Bevier Coal	850'-852'
Croweburg Coal	863'-865.5'
Fleming Coal	891'-893'
Mineral Coal	905.5'-907.5'
Bbj Coal	954'-956'
Rowe Coal	1077'-1079'
Riverton A Coal	1111'-1114'
Riverton B Coal	1123'-1125'
Riverton C Coal	1139'-1141'

RECEIVED
JUL 17 2006
KCC WICHITA