

6 070251

API NUMBER 15-192-20, 328-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW-NE-SE, SEC. 26, T. 7 S, R. 21 WE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name RALL Well # 1

Operator: BROUGHER OIL, INC.

County THOMAS 151.13

Name & Address P.O. DRAWER 1367

Well Total Depth 4650 feet

GREAT BEND, KANS.

Conductor Pipe: Size 0 feet

67530

Surface Casing: Size 8 5/8 feet 456

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated TAG # 1697

Plugging Contractor MOHAWK DRILLING INC License Number 6394

Address GREAT BEND, KANS.

Company to plug at: Hour: 1:30 PM Day: 17<sup>th</sup> Month: NOV. Year: 19 84

Plugging proposal received from RON TAUSCHER

(company name) MOHAWK DRILLING, INC (phone) 716-793-5610

were: 8 5/8" - 456 FT SP. CUL #/300 <sup>SK 60/</sup> 140 Pozmix GEL - CAC (BY HALIBURTON)

ORDER 220 <sup>SK 50/</sup> 150 Pozmix GEL - CA-CL - 1 <sup>SK 710</sup> CELE AND 8 5/8" PLUG.

SPOT WITH DRILL STEM-TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

No circulation problems, MISSISSIPPI WELLS, ELEV. 2979 - ANH. 2631

RECEIVED  
STATE CORPORATION COMMISSION  
11-26-1984

Plugging Proposal Received by M. Marion Schmidt

CONSERVATION DIVISION  
Wichita, Kansas  
Boik (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:30 PM Day: 17<sup>th</sup> Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 220 <sup>SK 50/</sup> 150 Pozmix GEL - CA-CL - 1 <sup>SK 710</sup> CELE + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM-TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

1<sup>ST</sup> PLUG @ 2670 <sup>SK</sup> #/300 CMT. - 2<sup>ND</sup> PLUG @ 1720 <sup>SK</sup> #/100 1 CELE

3<sup>RD</sup> PLUG @ 460 <sup>SK</sup> #/60 CMT, 4<sup>TH</sup> PLUG <sup>SOLID BRIDGE</sup> HULLS - PLUG @ 40 <sup>SK</sup> #/10 CMT.

10<sup>SK</sup> IN RAT HOLE - 10<sup>SK</sup> IN MOUSE HOLE - CIRCULATE BOTH.

CEMENTED BY HALIBURTON CMT.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If not) observe this plugging.

DATE 11-28-84

Signed M. Marion Schmidt  
(TECHNICIAN)  
Boik

INV. NO. 4960

11-21-84  
14