

6030643

API NUMBER ~~15-179-20648-00-00~~ 01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION/DONE/NESENESEC.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NESENESEC. 2, T 7 S, R 27 (W)E

3700' feet from S section line

260 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5232

Lease Name SNIFFIN Well # 3 SWO

Operator: PINTO PETROLEUM CO.

County SHERIDAN 74.75

Name & Address Box. 11184

Well Total Depth 2300' feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67211

Surface Casing: Size 8 5/8 feet 342'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS 67524

Company to plug at: Hour: PM Day: 6 Month: 1 Year: 19 85

Plugging proposal received from MARK

(company name) KELSO CASING. (phone) _____

were: 8 5/8 342' w/250sx. 4 1/2" @ 2300 w/450 PBD 2335' PERF. 2000' 72120'

CASING CEMENTED IN NO RECOVERY ORDER 150 SX. 60/40 Pdz 6% GEN.

3% ACC. 4SX. GEL 4SX. HULLS ALLIED CMT. CO. LARUE WATER HAULERS

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15PM Day: 6 Month: 1 Year: 19 85

ACTUAL PLUGGING REPORT MIX. & Pump Down 4 1/2" CASING 100SX. CMT. MIX. +

3SX. HULLS 4SX. GEL + 1SX. HULLS 50SX. CMT. MIX. MAX. PST 1200#

CLOSE IN 500# PLUG. COMPLETE.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JAN 14 1986
INV. NO. 12045

Signed Carl Goodrow 1-10-85
(TECHNICIAN)