

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20, 175-00-00

TECHNICIAN'S PLUGGING REPORT

SE-SE-SE, SEC. 30, T. 8 S, R. 15 WE
330 FEET FROM N(S) SECTION LINE R
330 FEET FROM W(E) SECTION LINE

OPERATOR LICENSE # 5184

LEASE NAME GRIFFIN WELL # A-2

OPERATOR: SHIELDS OIL PRODUCERS
NAME & ADDRESS: 326 MAIN
RUSSELL, MO. 67665
INC.

COUNTY: OSBORNE
WELL TOTAL DEPTH: 3400 FEET \$110.50
CONDUCTOR PIPE: SIZE 0 FEET
SURFACE CASING: SIZE 8 5/8 FEET 271 o.k.

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SHIELDS DRILLING CO LICENSE NUMBER 5184

ADDRESS 326 MAIN, RUSSELL, MO, 67665

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 24th MONTH: JUNE YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM BURTON BERRY

(COMPANY NAME) SHIELDS DRILLING CO (PHONE) 913-483-2141

WERE: 8 5/8" 271' 1/2" SR. CUC #1165ST 60/40 Poz + QUICK SET (BY ALLIED)
ORDERED 175ST 50/50 Pozmix 4% GEL-3% CA-CL AND 8 5/8" PLUG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUG
ELV. 1949 - ANH. 1209 - WAF TO BE A. K-C WELL

PLUGGING PROPOSAL RECEIVED BY Morgan Schmidt
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 8:15 AM DAY: 24th MONTH: JUNE YEAR: 19 83

ACTUAL PLUGGING REPORT ORDERED 175ST 50/50 Pozmix 4% GEL-3% CA-CL & 8 5/8" PLUG
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUG
1ST PLUG @ 1230 FT #1/25ST ENT. 2ND PLUG @ 840 FE #1/80ST ENT.
3RD PLUG @ 275 FT #1/40ST ENT. 4TH PLUG ^{Solid Bridge} Hulls Plug @ 40 FE #1/10
10ST IN RAT HOLE (CIRCULATE), 10ST IN MOUSE HOLE ENT.
(CEMENTED BY ALLIED CMT.) (CIRCULATE)

REMARKS: _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1983 6-27-83

CONSERVATION DIVISION
Wichita, Kansas

I (~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Morgan Schmidt
(TECHNICIAN) BOIC

INVOICED
DATE 7-8-83
INV. NO. 4765-W