

4-041535

11-9

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,946-00-00

SE SW NE /4 SEC. 35, 07 S, 26 W
2970 feet from S section line
1650 feet from E section line

Operator license# 5184 Lease Scheetz well # 1

Operator: Shields Oil Producers County Sheridan

Address: Shields Building Well total depth 3839 feet ^{124.76}
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 297 feet
w/160 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 9 Month: November Year: 93

Plugging proposal received from: Marvin Ratts

Company: Shields Oil Producers Phone:

Were: 4 1/2" casing set @ 3859' w/500 sxs. cement. Perf. @ 3783' -
3784'. W.L.M. @ 3790'. T.O.F. @ 2700'. Cement circulate top to bottom.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 200# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M, Day: 9, Month: November, Year: 93

Actual plugging report: Hooked-up to 4 1/2" casing. Squeezed 25 sxs.
cement with 200# hulls followed with 7 sxs. gel, followed with 125 sxs.
cement with 100# hulls. Max. 200#. S.I. 100#.
Hooked-up to 8 5/8" S.P. Pressured up to 500#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL STATE

I did] observe the plugging.

INVOICED
DATE NOV 23 1993
INV. NO. 39300

Dennis L. Hamel
(agent)

RECEIVED
NOV 17 1993
NOV 17 1993
CONSERVATION DIVISION
Wichita, Kansas