

6070270

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20, 774-00700
SE-NE-SW, SEC. 25, T. 7 S, R 26 W

1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name JOHN C. SCHEETZ Well # A #1

Operator: DIAMOND SHAMROCK EXP. CO.

County SHERIDAN

Name & Address P.O. Box 400

Well Total Depth 3983 ^{129.45} feet

AMARILLO, TEXAS.

Conductor Pipe: Size 0 feet

79188-0001

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ALLEN DRILLING CO. License Number 5418

Address Box 1389, 1105 WALNUT, GREAT BEND, MS 67530

Company to plug at: Hour: 11:00 PM Day: 6th Month: DEC. Year: 19 84

Plugging proposal received from CRAIG CHRISTOPHER

(company name) ALLEN DRILLING INC (phone) 316-792-5681

were: 8 5/8" 328' 50' CUL #1/250 ENT COMMON GEL-CA-CL - (BY ALLIED CMT.)

ORDER 210 1/50 FORMIX GEL-CA-CL-1 GEL AND 8 5/8" PLUG.

SPOT WITH DRILL STEM-TURN HOLE OVER-HEAVY MUD BETWEEN ALL PUGS.

LOWER SUCTION BEFK RECONDITIONING HOLE, NO ARBUCKLE (KC WELL)

NO CIRCULATION PROBLEMS, ELV. 2548-7NH 2200,

Plugging Proposal Received by Marion J. Lueders
(TECHNICIAN)

Plugging Operations attended by Agent: All _____ Part _____ None X

Operations Completed: Hour: 9:00 PM Day: DEC. Month: 6th Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 210 1/50 FORMIX GEL-CA-CL-1 GEL

AND 8 5/8" PLUG, 1st PLUG @ 2220' 1/30' ENT, 2nd PLUG @ 1390' 1/100' ENT

WITH 1st GEL, 3rd PLUG @ 330' 1/60' ENT, 4th PLUG @ 40' 1/10' ENT

10' IN RAT HOLE (CIRCULATE) CEMENTED BY ALLIED CMT. [TICKET NO 40751]

RECEIVED STATE CORPORATION COMMISSION

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 1-3-89

Signed Marion J. Lueders
(TECHNICIAN)
DLIC

INV. NO. 6264

12-6 JAN 14 1985

DEC 17 1984
CONSERVATION DIVISION
Wichita, Kansas