

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20,764 -00-00  
NW NE SE Sec. 35, T 7 S, R 26 W/EX  
2310 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name John C. Scheetz Well # 2

Operator: Diamond Shamrock  
Name & P.O.BOX 631  
Address Amerillo, Tx. 79173

County Sheridan

Well Total Depth 3970 feet 129.03

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie License Number 5422

Address 801 Union Center, Wichita, Ks.

Company to plug at: Hour: AM Day: 25 Month: September Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO James Skees

(company name) Diamond Shamrock (phone) \_\_\_\_\_

were: Order 185 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel, 1 sk hulls and  
8 5/8" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs, with  
good circulation and no fluid loss.

Signed \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 8:45 AM Day: 25 Month: September Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 2180 w/25 sks

2nd plug @ 1370 w/100 sks 1 sk flo-cel

3rd plug @ 380 w/40 sks

4th plug @ 40 w/8 5/8" plug 1 sk hulls and 10 sks cmt

10 sks in Rat Hole

Remarks: Cemented by Allied.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 01 1984  
OCT 01 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Gilbert P. Leiker  
(TECHNICIAN)

INVOICED

DATE 10-5-84

INV. NO. 4046

9-25

FORM CP-2/3  
Rev. 9-82

4-28-84

26