

6 030642

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20491-00-07

NEENE SEC. 2, T. 7 S, R. 27 (WE)

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5232

Lease Name SNIFFIN Well # 2 OWAO

Operator: PINTO PETROLEUM CO.

County SHERIDAN 132.93

Name & Address Box. 11184

Well Total Depth 4090 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67211

Surface Casing: Size 8 5/8 feet 283'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS 67524

Company to plug at: Hour: PM Day: 6 Month: 1 Year: 19 86

Plugging proposal received from MARK

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 283 CWC 4 1/2 @ 4085 4/200SX. PBTD 4032 PERF. 3888' / 3930'

ORDER SAND & COM. CMT. SHOOT & RECOVER PIPE ORDER 180 SX. 60/40

POZ. 6 1/2 GEL 3 1/2 CC 40 SX. GEL 4 SX. HULLS 8 5/8 W.P. ALLIED CMT CO.

LARUE WATER TRUCKS

Plugging Proposal Received by Carl Goodlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:PM Day: 6 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3830' SPOT 4 SX. COM. CMT. ON SAND
W/BAILER. SHOT & RECOVERED 1400' OF 4 1/2" CASING.

MIX. & Pump Down 8 5/8 - 3 SX. HULLS 22 SX. GEL. 100 SX. CMT. MIX. 1 SX. HULLS -
18 SX. GEL. 8 5/8 W.P. 80 SX. CMT. MIX. MAX. PST 600* CLOSE IN PST 300*
PLUG. COMPLETE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986

INV. NO. 12046

Signed Carl Goodlow
(TECHNICIAN)
JAN 13, 1986
CONSERVATION DIVISION
WICHITA, KANSAS

18
1-10-86
mgj