

6 030641

API NUMBER 15-79 20588-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWSENE SEC. 2, T. 7 S, R. 27 (W)

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5232

Lease Name SNIFFIN Well # 1

Operator: PINTO PETROLEUM CO.

County SHERIDAN 132.93

Name & Address Box 11184

Well Total Depth 4090' feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67211

Surface Casing: Size 8 5/8 feet 300'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS 67524

Company to plug at: Hour: PM Day: 6 Month: 1 Year: 19 86

Plugging proposal received from MARK

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 300' w/ 200 SX. 4 1/2 @ 4084 w/ 100 SX. PERF. 3846' / 4040'

ORDER SAND & COM. CMT. SHOT & RECOVER PIPE ORDER 180 SX. 60/40 PER
6 GEL 3% CC 40 SX. GEL 4 SX. HULLS 8 5/8 W.P. ALLIED CMT. CO. LARUE
WATER TRUCK.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 PM Day: 6 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT DUMP SAND TO 3800' SPOT 4 SX. COM. CMT. ON SAND W/ BAILER
SHOT & RECOVERED 1400' OF 4 1/2" CASING.

MIX. & PUMP DOWN 8 5/8 - 3 SX. HULLS 22 SX. GEL - 100 SX. CMT MIX. + 1 SX. HULLS
18 SX. GEL. 8 5/8 W.P. 80 SX. CMT. MIX. MAX. PSI 500TH CLOSE IN 200TH PSI
PLUG COMPLETE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986

INV. NO. 12044

JAN 13, 1986

Signed Carl Goodrow
(TECHNICIAN)

17
1-10-86
mgg